BRUHAT BANGALORE MAHANAGARA PALIKE

NAME OF WORK:- Improvements to Footpath in Ward No. 11, Byatarayanapura.

MODIFIED SCHEDULE - B

Item No	Description of Work	Unit	Total Quantity as per Approved	Rate Quoated by Sri Venkateshappa. A	
				In Figures	In Words
1	Removing and resetting of footpath slab (Approved arrival rate)	Sqm	720.00	200.00	Rupees Two Hundred Only
2	Earth work Excavation by manual means for drains,canals, waste weir, draft, approach channels, key trenches, foundation of bridges and such simillar works in all kinds of soils , as per drawing and technical specifications, including setting out, shoring, strutting, barricading, caution lights, removal of stumps and other deleterious matter, excavated surface leveled and sides neatly dressed disposing off the excavated stuff or sorting & stacking the selected stuff for reuse in a radius of 50 m and lift upto 1.5 m including cost of labour, tools & other appurtenaces required to complete the work.	Cum	266.00	180.00	Rupees One Hundred Eighty Only
3	Providing and laying in position plain cement concrete for levelling course for all works in foundation. The granite / trap / basalt crushed graded coarse aggregates and fine aggregates as per relevant IS Codes machine mixed, laid in layers not exceeding 150 mm thickness, well compacted using plate vibrators, including all lead & lifts, cost of all materials of quality, labour, Usage charges of machineries, curing, and all the other appurtenances required to complete the work as per technical specifications. (The cost of steel reinforcement & formwork shall be paid separately **Mix 1:3:6 (M10) Using 20 mm nominal size graded crushed coarse aggregate**	Cum	24.00	5500.00	Rupees Five Thousand Five Hundred Only
	Qty above 125%		15.90	4830.19	Rupees Four Thousand Eight Hundred Thirty And Paise Nineteen Only
4	Removing and resetting of kerb stone (Approved arrival rate)	Mtrs	150.00	100.00	Rupees One Hundred Only
5	Providing and laying in position Reinforced cement concrete for all Sub structures of building, Irrigation works, Sub structure works of bridges, Drain works & other parallel works from 0.50m to 3.50 m height. The granite/trap/basalt crushed graded coarse aggregates and fine aggregates as per relevant IS Codes machine mixed with super plasticisers, laid in layers, well compacted using needle vibrators, providing weep holes wherever necesary, including all lead & lifts, cost of all materials of quality, confirming to the requirements of relevant IS codes, labour, Usage charges of machinery, curing and all other appurtenances required to complete the work as per technical specifications. M20 (The cost of steel reinforcement & formwork to be paid separately)	Cum	83.79	6500.00	Rupees Six Thousand Five Hundred Only
6	Supplying, Fitting and Placing un-coated TMT bar Reinforcement in sub-structure complete as per Drawing and Technical Specifications.		5.03	85000.00	Rupees Eighty Five Thousand Only

Signature of the Contractor

Executive Engineer
ಕಾರ್ಯಪಾಲಕ ಅಭಿಯಂತರರು
ಬ್ಯಾಟರಾಯನಪುರ ವಿಭಾಗ,
ಬೃ.ಬೆ.ಮ.ಪಾ, ಬೆಂಗಳೂರು.

Item No	Description of Work	Unit	Total Quantity as per Approved	Rate Quoated by Sri Venkateshappa. A	
				In Figures	In Words
7	Providing and Fixing pre cast Covering Slab made out of CC 1:2:4 with 10cm thick and Finishing cutting, including form work,curing, including cost of all materials, labour, hire charges of machinery, loading, unloading, lead and lift, transportation etc, copmplete.	Sqm	239.40	1800.00	Rupees One Thousand Eight Hundred Only
8	Supplying and fixing M15 grade precast cement concrete 600 x 300 x 150 mm Kerb Stone for Roadway, Sidewalls and gutters fixed with CM 1:3 fixed and finsihed in line as per direction of Engineer in charge.	Mtrs	266.00	330.00	Rupees Three Hundred Thirty Only
9	Painting Two Coats on New Concrete Surfaces Painting two coats after filling the surface with synthetic enamel paint in all shades on new plastered concretesurfaces.	Sqm	93.10	85.00	Rupees Eighty Five Only
10	Supplying and filling in plinth with sand under floors, foundation of Bridges including watering, ramming, consolidating and dressing complete	Cum	0.00	1700.00	Rupees One Thousand Seven Hundred Only
11	Providing and laying heavy duty cobble stones 60mm thick interlock pavers, using cement and course sand for manufacture of blocks of approved size, shape and colour with a minimum compressive strength of 281 kg per m2 over 50mm thick sand bed (average thickness) and compacting with plate vibrator having 3 tons compaction force thereby forcing part of sand underneath to come up in between joints, final compaction of paver surface joints into its final level , including cost of materials, labour and Usage charges of machinery complete as per specifications		0.00	510.00	Rupees Five Hundred Ten Only
12	Loading and Unloading of Stone Boulder / Stone aggregates / Sand / Kankar / Moorum. (Tipper 14 m3)	Cum	239.40	60.00	Rupees Sixty Only
13	Cost of Haulage Excluding Loading and Unloading Taking output 18 t load and lead 10 km = 180 t.km	T.Km	306.43	62.00	Rupees Sixty Two Only

Signature of the Contractor

Executive Engineer
Byatarayanapura Division